Gardner Denver 500 GEOTHERMAL DRILLING RIG Capacity 9,000 Feet

DRAWWORKS

- Gardner Denver 500
- 4 Speed 750 DRD Allison Transmission, w/right angle Gear Box Rated @ 1000 HP.

POWER

- New 750 HP Series 60 Detroit Engine

MAST

 Lee C. Moore 126' x 12' base, 280,000# Static Hook Load, Category 4 – Certified January, 2012.

CROWN BLOCK

- New Lee C. Moore five (5) Sheaves

SUBSTRUCTURE

- New Dreco One Piece 12.6' W x 13.6'H X40'L
- Rotary Table Cap 280,000# set back 225,000#

ROTARY TABLE

- Gardner Denver 17 ½"

TRAVELING BLOCK/HOOK

- McKissick 150 Ton

SWIVEL

- National P-200

KELLY

- New 5 1/4" Hex, 5 1/4" Varco Bushing
- Upper and lower Kelly cock valves

KELLY SPINNER

- New Kelly Spinner forward & reverse (New)

MUD PUMP

- #1 Pump PZ-8 Triplex
- Power: 850 HP 3412E CAT Engine New
- Specs: 7"x8", 2.96 GPR @ 100%
- 0.07 BBL stk:
- Max. psi 6" liners 2717 psi
- All housed within 12'6" W x 12' 2" H x 43' L Steel Building with Lighting, Steam Heaters and Parts Storage. (See Spec Attachment)
- #2 Pump MM 550 IDECO Duplex
- Power: 3412 CAT Engine
- Specs: 71/4" x 15", 6.7 GPR @ 100%
- Max. psi 6" liners 1845 psi
- All housed in 12'1" W x 12' 3" H x 40' 2" L Steel Building with Lighting, Steam Heaters and Parts Storage. (See Spec Attachment)

MUD TANK SYSTEM MI SWACO

- One (1) 550 BBL/4 Compartment Tank
- One (1) Mi Swaco Mongoose Shaker
- Model MPR 932 4 Screen 46" W x 23" H x 92" L
- Four (4) Mud Guns w/two (2) Agitators
- Two (2) 5"x 6" Gallagher Centrifugal Pumps each driven by 60 HP Motors. All housed within 12' W x 12' 2" H x 9' L Steel Building Incorporated into mud tank with lights, Steam Heat in Addition opposite end of mud tank 12' W x 12' 2" H x 4' L Storage Compartment with Shelving.

RESERVE PIT PUMP

- Centrifugal Pump 3x4x11" imp, driven by 25 HP electric motor

FRESH WATER TANK

 One (1) 350 BBL water tank with scissor top dog house opposite end tool room, 2 20 HP Centrifugal pumps driven by electric motor, skid mounted

FUEL TANK

- One 10,000 gallon fuel tank with 2 Centrifugal filter system; pumps driven by electric motors, skid mounted

GENERATOR

- Series 60 Detroit Engines 600 HP 400 KW, Marathon Generator
- Housed in 10'W x 8'11"H x 41'2"L combination building.

BOP EQUIPMENT

Accumulator:

- Five (5) Station 150 gallon capacity electric @ air pumps

Choke Manifold:

- 4 1/16" 5,000 psi WP dual choke one fix, one adjustable

Ram Preventers:

- Shaffer LWS Double Ram 11", 5,000 psi.

Annular Preventer:

- Hydril GK 11" 3,000 psi WP

TUBULARS:

- 9,000 - 4 ½" OD New G105 XH

DRILL COLLARS

6 ¼" XH, 8" 6 5/8" Reg

PIPE TUBS

- Three (3) Pipe Tubs

DRILL LINE

- 11/8" EIPS,

PIPE RACKS

- Two (2) Sets Pipe Racks

_

HANDLING TOOLS

- Tongs
- Elevators
- Slips
- Safety Clamps

AIR COMPRESSOR

- Two (2) Quincy 370 air compressors, one electric and one mechanical

WINTERIZATION PACKAGE

- Complete wind wall enclosures
- Steam heaters

BOILER

- 125 HP Cleaver Brooks with 100 BBL holding water tank

SURVEY MACHINE

- Five Star 092 - 15,000 feet

MATTING BOARDS

- 3 8'X40'
- 1 8'X38'
- 2 8'X10'

AUXILLARY EQUIPMENT

- One (1) Air Hoist 4,000# new
- Two (2) Hydraulic Hoists; 4,200# each

LOADER WITH FORKLIFT

- 544 John Deere Loader

RIG MANAGERS LIVING QUARTERS/OFFICE

- One Teton 14' x 50', total electric, skid mounted